

PROJECT NAME

(item 3) Beverly Park 230-115 kV Substation

PROJECT DESCRIPTION

Expand the existing 115 kV switching station and add a 230-115 kV 300 MVA transformation. The 230 kV source will be from the BPA Snohomish Substation. An existing 115 kV line from BPA Snohomish to the Glenwood Tap will be converted to 230 kV. The 115 kV line serving the Glenwood Tap will then be configured to be served from the Beverly Park 115 kV bus. BPA will provide the 230 kV connection at the BPA Snohomish Substation.

Sponsor

Snohomish PUD No. 1

Commitment level

High - based on present forecasts the construction is committed to the schedule. However changes in load and generation could impact schedules.

Schedule Completion Date

November 2011

Is Project "Fast Track"

No

Project Implementation Stage

Construction is Underway

Location

See item (3) on attached map

"Map of Major Projects Transmission Expansion 2008-2021"