

**PROJECT NAME** (item 4) Swamp Creek 115 kV Switching Station

**Program Description**

Construct a six 115 kV breaker switching station with a ring bus arrangement using GIS technology (four breakers only needed for phase one work). Future construction will include one 115 kV line position will terminate a new 115 kV line from the Paine Field Area and one new 115 kV termination of a 230kV / 115 kV transformer. This switching station will terminate 115 kV lines from SnoKing (2 Lines), Halls Lake (1 line) and from Beverly Park (1 line).

**Sponsor** Snohomish PUD No. 1

**Commitment level** Medium - based on present forecasts the construction is committed to the schedule. However changes in load and generation could impact schedules.

**Schedule Completion Date** November 2013

**Is Project "Fast Track"** No

**Project Implementation Stage** Planning Stage, Construction begins in 2009

**Location** See item (4) on attached map  
"Map of Major Projects Transmission Expansion 2008-2021"